


# Windows and doors without thermal break

in steel and stainless steel



Entrance doors in stainless steel  
Linkin Park, Beijing, China

**forster**norm  
**forster**presto

**forster**

# Doors, windows and glazings without thermal break


**ROBUST AND ELEGANT.** forster presto is the complete profile system with fittings and accessories for flush-fitting single- and double-leaved doors, glazed walls, porches and windows which do not require thermal break. These elements stand for elegance and safety and satisfy the most stringent requirements with regard to extreme constant use.

## Technical details


Material options	Steel bright / stainless steel, grinded, grain 220-240
Performance specifications*	Sound insulation up to Rw 44dB Smoke-resistant doors RS-1/RS-2 (DIN 18095) and S <sub>200</sub> (EN 1634) Fire-resistant doors and screens E30–E120/EW30–EW60 acc. to DIN 1634 Flush mounted sheet metal door E30 Fire-resistance: classification reports according to EN 13501-2 Burglar-resistant doors RC 2-3 according to EN 1627-1630 Long-term performance C5 according to EN 1191 CE-Marking according to EN 14351-1
Fittings	Fittings to match the system Attractively shaped stainless steel handle set and slender weld-on door hinges as well as concealed hinges Concealed door-closing systems
System properties	Extremely economical manufacture with no special equipment Extremely slender visible section widths (frame/leaf section measurement only 120 mm) Individual surface treatment

\*Refer to country-specific approvals



forster presto 50



forster presto 60



forster presto 60S



Glazings and high level acoustic insulation doors and abutments  
Opera Palacio de las Artes Reina Sofia, Valencia, Spain


# Doors, windows and glazings without thermal break

**VERSATILE AND LOW-COST.** The forster norm profile assortment is suitable for the construction of doors, screens and windows without thermal break. The right choice of profiles enables you to build many different kinds of conventional casement windows or window bands, as well as doors and partition walls. The variety of profiles in different section depths means that your creativity knows no bounds and offers endless combination possibilities.

## Technical details

Material options	Steel bright
Performance specifications*	CE-Marking according to EN 14351-1
Fittings	Both fittings made to match the system and usual commercial fittings can be used
System properties	Section depths: 34, 40, 50 and 60 mm Case widths: from 10 to 95 mm

\*Refer to country-specific approvals



800 window elements with arches  
Tour & Taxis, Brussels, Belgium

Fire-resistant door forster presto  
Rechtbank, Zwollen, The Netherlands



Doors and glazings  
Lakenhallen, Ieper, Belgium



Fire-resistant doors forster presto EW60  
School De Dukdalf, Dronten, The Netherlands

908364/10012682/01-18